


PHOTOGRAPH THIS SHEET

AD-A113 212

DTIC ACCESSION NUMBER



LEVEL



INVENTORY

FN-TR-ETB-1

DOCUMENT IDENTIFICATION

Contract F04704-80-C-0006

29 Aug. 80


DISTRIBUTION STATEMENT A

Approved for public release;  
Distribution Unlimited

DISTRIBUTION STATEMENT

ACCESSION FOR	
NTIS	GRA&I <input checked="" type="checkbox"/>
DTIC	TAB <input type="checkbox"/>
UNANNOUNCED	<input type="checkbox"/>
JUSTIFICATION	
BY	
DISTRIBUTION /	
AVAILABILITY CODES	
DIST	AVAIL. AND/OR SPECIAL
A	

DISTRIBUTION STAMP



DATE ACCESSIONED



005

DATE RECEIVED IN DTIC

PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-DDA-2

AD A113212

CONFIDENTIAL

FN-TR-ETB-1

PROGRESS REPORT  
GEOTECHNICAL STUDY FOR  
MOBILITY TEST TRACKS  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

Prepared for:

U.S. Department of the Air Force  
Ballistic Missile Office  
Norton Air Force Base, California 92409

Prepared by:

Fugro National, Inc.  
3777 Long Beach Boulevard  
Long Beach, California 90807

29 August 1980

**FUGRO NATIONAL INC**

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER <del>FN-TR-ETB-1</del> FN-TR-ETB-1	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Progress Report Geotechnical Study for Mobility Test Tracks ETB mobility study New Test site, NV.		5. TYPE OF REPORT & PERIOD COVERED Final
7. AUTHOR(s) Fugro National		6. PERFORMING ORG. REPORT NUMBER FN-TR-ETB-1
9. PERFORMING ORGANIZATION NAME AND ADDRESS Ertec Western Inc. (formerly Fugro National) P.O. Box 7765 Long Beach Ca 90807		8. CONTRACT OR GRANT NUMBER(s) F04704-30-C-0006
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Department of the Air Force Space and Missile Systems Organization Ballistic Missile Office Norton AFB Ca 92409 (SAAASO)		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 64312 F
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE 24 Aug 80
		13. NUMBER OF PAGES 35
		15. SECURITY CLASS. (of this report)
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Distribution Unlimited		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)  Distribution Unlimited		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Geology, <sup>res.</sup> test track, Pit Log <sup>site</sup> 5, Density Results, <del>FOR</del> California Bearing Ratio, Cone Penetration Tests, moisture content tests, triaxial compression tests		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) <del>Summary:</del> results of a geotechnical study for mobility test tracks at the south west corner of the Nevada Test site, Lathrop Well, Nevada give the suitability of the soils for these test tracks.		

FOREWORD

This report was prepared for the Department of the Air Force, Ballistic Missile Office (BMO) under Contract No. F04704-80-C-0006. It is a progress report and presents the results of a geotechnical study performed at the mobility test tracks in Engineering Test Bed at Nevada Test Site, Nevada. Further studies are scheduled during and after the mobility tests. It is planned to prepare additional progress reports following these studies.

# TABLE OF CONTENTS

	<u>Page</u>
FOREWORD .....	i
1.0 <u>INTRODUCTION</u> .....	1
1.1 Background .....	1
1.2 Test Tracks .....	1
1.3 Scope .....	3
2.0 <u>GEOLOGY</u> .....	4
2.1 General .....	4
2.2 Test Track B .....	6
2.3 Test Track C .....	6
2.4 Test Track G .....	7
3.0 <u>FIELD INVESTIGATION</u> .....	8
4.0 <u>LABORATORY INVESTIGATION</u> .....	15
5.0 <u>DISCUSSION OF RESULTS</u> .....	27
5.1 Test Track B .....	27
5.2 Test Track C .....	28
5.3 Test Track G .....	34
5.4 Virgin Desert .....	35

## LIST OF APPENDICES

### APPENDIX

A	Test Pit Logs
B	Results of Cone Penetration Tests
C	Results of Laboratory Tests

## LIST OF TABLES

<u>Table Number</u>		
3-1	Field Test Results, Track B .....	13
3-2	Field Test Results, Track C .....	14
4-1	Relative Density Results, Track B .....	17
4-2	Relative Density Results, Track C .....	23

## TABLE OF CONTENTS (Cont.)

Page

## LIST OF TABLES

Table  
Number

5-1	Estimated CBR and $\phi$ , Track B .....	29
5-2	Estimated CBR and $\phi$ , Track C .....	31
5-3	Comparison of Pre- and Post-Mobility Test CPTs, Track C .....	33

## LIST OF FIGURES

Figure  
Number

1-1	Location Plan .....	2
2-1	Topographic Map, ETB Mobility Study Area, NTS .....	5
3-1	Location of Field Activities, Track B .....	9
3-2	Location of Field Activities, Track C .....	10
3-3	Location of Field Activities, Track G and Virgin Desert .....	11
4-1	Grain Size Curves, Track B .....	16
4-2	CBR Curve - Soaked Tests, Track B .....	18
4-3	CBR Curve - Unsoaked Tests, Track B .....	19
4-4	Triaxial Compression Test Results, Track B ....	20
4-5	Grain Size Curves, Track C .....	22
4-6	CBR Curve - Soaked Tests, Track C .....	24
4-7	CBR Curve - Unsoaked Tests, Track C .....	25
4-8	Triaxial Compression Test Results, Track C ....	26

## 1.0 INTRODUCTION


### 1.1 BACKGROUND

This progress report presents the results of the geotechnical study performed at the three road test tracks at Engineering Test Bed (ETB) in Nevada Test Site, Nevada (see location map in Figure 1-1). The test tracks are part of the mobility study planned by the Boeing Company in which a Terex 33-15 vehicle will traverse the tracks. The test tracks are located northeast of the previously constructed prototype vertical shelter and loop road. This study was performed to determine the geotechnical properties of the soils at the test tracks. Further studies are planned during and after the mobility tests.

### 1.2 TEST TRACKS

The three test tracks are designated as test tracks B, C, and G and were constructed by small amounts of cut and fill. Neither compaction nor treatment of the graded soils was performed. However, the surficial soils may have been compacted slightly due to the operation of construction equipment. Tracks B and C were constructed prior to April 1980 while track G was constructed between 12 August and 17 August 1980. Track B is 1900 feet long and is located in the flank of the Little Skull Mountain. It consists of two sections; one from Station 0+00 to 6+00 with four percent grade and the second from Station 7+00 to 19+00 with one percent grade. The two sections are approximately perpendicular to each other. Tracks C and G are 1200 feet long located in the center of the valley, and have 0.5 percent grade.





### 1.3 SCOPE

The scope of this study consisted of the following:


- o Field investigation: Cone Penetration Tests (CPTs), test pits and in situ field density and moisture content tests;
- o Laboratory investigation: Classification, compaction, relative density, California Bearing Ratio (CBR), and triaxial compression tests;
- o Data analysis: Summary of the field conditions, physical and engineering properties of soils at the test tracks, and discussion on pre- and post-mobility test CPTs at track C.


## 2.0 GEOLOGY


### 2.1 GENERAL


The three test tracks, are in Jackass Flats located in the south west corner of the Nevada Test Site. The area is just north of U.S. Highway 95 at its junction with State Highway 29 at Lathrop Wells, Nevada (Figure 2-1). Jackass Flats is located within the Great Basin physiographic province, an area characterized by large fault-block mountain ranges separated by aggrading alluvial basins. The test tracks are bounded on the north by the Little Skull Mountains which are composed chiefly of Tertiary basalt with minor ash-flow tuffs. The Striped Hills are located in the southern end of the site and consist of lower-Paleozoic limestone and dolomite. The western boundary is along Fortymile Wash, a deeply incised channel which flows southward into the Amargosa Desert.


The principal surficial geologic units are alluvial fan deposits of young (A5y) to intermediate (A5i) age. These deposits consist of sand and gravel, moderately to well-cemented by caliche. Overlying the alluvial fan deposits is a veneer of eolian sand (A3s) which ranges in thickness from zero to over 5 feet. Fluvial or stream channel deposits (A1) consisting of loose sand, gravel, cobbles, and boulders, are found along Fortymile Wash and Topopah Wash as well as numerous smaller drainages which generally flow south-southwesterly across the site.

























## 2.2 TEST TRACK B

Test track B is located along the southwestern flank of the Little Skull Mountain (Figure 2-1). The underlying deposits consist of a thin mantle of young alluvial fan material (A5y) overlying intermediate-age alluvium (A5i). Test pit logs indicate that the soil is a gravelly sand (SP-SM and SW-SM). Stage I to III caliche, with local occurrences of Stage IV caliche, exist in this sand sometimes throughout the stratum or in the form of layers. This well-developed caliche, occurring at shallow depths, indicates that the uncemented younger alluvial fan deposit at the surface is very thin and is underlain by cemented intermediate alluvial fan material. Caliche development is somewhat more advanced than is generally encountered in the Nevada-Utah siting region, probably due to abundant local sources of calcium carbonate. Decomposition of basalt clasts in alluvium derived from the Little Skull Mountain and active eolian aggradation of calcareous dust on fan surfaces provide calcium carbonate needed for caliche formation.

## 2.3 TEST TRACK C

Test track C is located in the center of the valley adjacent to the Lathrop Wells Road and northeast of the prototype vertical shelter test bed (Figure 2-1). A thin mantle of poorly graded eolian sand (A3s) up to 5 feet thick overlies intermediate age alluvial fan deposits. Fortymile Wash has incised deeply into the intermediate fan surface indicating that the surface of the fan has been abandoned as a surface of material transport for a long period of time. A moderate to well-cemented caliche

horizon (Stage III and local occurrences of Stage IV) occurs at the base of the eolian deposits. The source of calcium carbonate in this extensive caliche deposit is in part from calcareous dust and sand blowing northward from the Amargosa Desert and from basic volcanic rocks in the alluvium. This relatively abundant source of calcium carbonate resulted in accelerated development of caliche in the soil profile.

#### 2.4 TEST TRACK G

Test track G is located approximately 85 feet northeast of track C (see Figure 2-1). The geology is essentially the same for both tracks C and G.


### 3.0 FIELD INVESTIGATION

The first phase of the field investigation, consisting of test pits, field density and moisture content tests, and was performed for test tracks B and C between 28 April and 1 May 1980. The second phase of investigation (15 to 17 August 1980) was performed following mobility tests on track C. It consisted of CPTs at test track C, the newly constructed track G, and in the virgin desert (undisturbed ground) northeast of track G. The locations of the field activities are shown on Figures 3-1 through 3-3 and are summarized below:


<u>Test Track or Location</u>	<u>Total Length (ft)</u>	<u>Activity</u>	<u>Total Number</u>	<u>Depth (ft)</u>
B	1900	Test Pit	8	2.0 to 5.4
		In Situ Density and Moisture	9	—
		Disturbed Bulk Sample	14	—
		CPT	50	0.8 to 10.5
C	1200	Test Pit	4	3.5 to 6.0
		In Situ Density and Moisture	12	—
		Disturbed Bulk Sample	15	—
		CPT (pre-mobility testing)	42	3.8 to 6.4
		CPT (post-mobility testing)	42	2.6 to 5.5
G	1200	CPT (pre-mobility testing)	18	2.9 to 5.6
Virgin Desert	—	CPT	7	4.4 to 6.0

The methods of excavating test pits, sampling, and logging as well as performing in situ density and moisture content tests, were similar to those used presently in the ongoing MX Field Verification Program in Nevada and Utah valleys and are described in Appendix A. The CPTs were performed by the same equipment






PROFILE



STATION  
(1 INCH = 200 FEET)


**PROFILE**



ROAD WIDTH 33 FEET  
(SCALE: 1 INCH = 20 FEET)

STATION  
(SCALE: 1 INCH = 200 FEET)

7+00 8+00 9+00 10+00 11+00 12+00 13+00 14+00 15+00 16+00 17+00 18+00 19+00




PLAN

ROAD WIDTH 33 FEET (APPROXIMATE)  
(SCALE: 1 INCH = 10 FEET)

STATION  
(SCALE: 1 INCH = 200 FEET)

0 10+00 11+00 12+00 13+00 14+00 15+00 16+00 17+00 18+00 19+00



## PLAN

## EXPLANATION

- ▲ TEST PITS (P)
- CONE PENETRATION TESTS (C)

LOCATIONS OF FIELD ACTIVITIES AND PROFILE  
TEST TRACK B, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE BMD


FIGURE  
31

**FUGRO NATIONAL, INC.**


3

4


APPROXIMATE  
LOCATION, TEREX  
TREAD MARK



## PLAN



## PROFILE




ROAD WIDTH 33 FEET (APPROXIMATED)  
(SCALE: 1 INCH = 10 FEET)

### EXPLANATION

- ▲ TEST PITS (P)
- CONE PENETRATION TESTS (C)

#### EXAMPLE:

C-P-1 PRE-MOBILITY TEST CPT  
C-P-1P POST MOBILITY TEST CPT



### PROFILE


LOCATIONS OF FIELD ACTIVITIES AND PROFILE  
TEST TRACK C, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - DMO

FIGURE  
3-2


**FUGRO NATIONAL, INC.**

2



(SCALE 1 INCH = 200 FEET)

**PLAN**



# EXPLANATION

○ CONE PENETRATION TESTS (C)

LOCATIONS OF FIELD ACTIVITIES  
TEST TRACK G AND VIRGIN DESERT  
ETB MOBILITY STUDY, NEVADA TEST SITE, NEVADA

MA SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE DMO

FIGURE  
3-3

**FUGRO NATIONAL, INC.**



used in the MX Field Verification Study. The equipment and method of cone penetration testing are described in Appendix B. The logs of the test pits and CPTs are included in Appendices A and B, respectively. The depths of the test pits and CPTs were limited by the capability of the equipment when they encountered the hard strata of caliche as shown in the profiles for test tracks B (Figure 3-1) and C (Figure 3-2).

The in situ density and moisture content test results are shown in Tables 3-1 and 3-2 for test tracks B and C, respectively. These tables also include the average cone end bearing resistance ( $q_c$ , tsf) from CPTs at the corresponding locations and depths of in situ density tests.

		INDIVIDUAL TEST RESULTS								RANGE OF RESULTS	AVERAGE
TEST PIT NUMBER		B-P-1	B-P-2	B-P-3	B-P-4	B-P-5	B-P-6	B-P-7	B-P-8		
CORRESPONDING CPT		B-C-37	B-C-4	B-C-39	B-C-40	B-C-26	B-C-22	B-C-44	B-C-34		
DEPTH INTERVAL (ft.)		[1.0-1.5]									
CATEGORY	Y <sub>d</sub> (pcf)	115.9	—	113.5	105.2	114.5	—	109.6	99.9	99.9 ~ 115.9	109.8
	M/C (%)	8.0	—	7.0	4.8	7.0	—	5.4	4.7	4.7 ~ 8.0	6.2
	AVERAGE q <sub>c</sub> (tsf)	330	—	300	260	450	—	260	550	260 ~ 550	358
DEPTH INTERVAL (ft.)		[2.0-2.5]									
CATEGORY	Y <sub>d</sub> (pcf)	—	—	—	104.8	—	93.7	—	—	93.7 ~ 104.8	99.3
	M/C (%)	—	—	—	3.0	—	3.2	—	—	3.0 ~ 3.2	3.1
	AVERAGE q <sub>c</sub> (tsf)	—	—	—	110	—	260	—	—	110 ~ 260	185
DEPTH INTERVAL (ft.)		[3.0-3.5]									
CATEGORY	Y <sub>d</sub> (pcf)	—	—	—	112.1	—	—	—	—	112.1	112.1
	M/C (%)	—	—	—	2.0	—	—	—	—	2.0	2.0
	AVERAGE q <sub>c</sub> (tsf)	—	—	—	265	—	—	—	—	265	265

#### EXPLANATION

Y<sub>d</sub> DRY DENSITY

M/C MOISTURE CONTENT

q<sub>c</sub> CONE END BEARING RESISTANCE

FIELD TEST RESULTS  
TEST TRACK B, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMO

TABLE  
3-1

**FUGRO NATIONAL, INC.**

		INDIVIDUAL TEST RESULTS				RANGE OF RESULTS	AVERAGE
TEST PIT NUMBER		C-P-1	C-P-2	C-P-3	C-P-4		
CORRESPONDING CPT NUMBER		C-C-38	C-C-20	C-C-36	C-C-28		
DEPTH INTERVAL (ft.)		[1.0-1.5]					
CATEGORY	Y <sub>d</sub> (pcf)	110.2	105.0	108.5	97.9	97.9 ~ 110.2	105.4
	M/C (%)	4.9	5.0	5.6	5.8	4.9-5.8	5.3
	AVERAGE q <sub>c</sub> (tsf)	90	140	110	100	90-140	110
DEPTH INTERVAL (ft.)		[2.0-2.5]					
CATEGORY	Y <sub>d</sub> (pcf)	108.4	107.6	100.0	104.8	100.0 ~ 108.4	105.2
	M/C (%)	6.7	5.7	6.1	6.3	5.7-6.7	6.2
	AVERAGE q <sub>c</sub> (tsf)	90	160	100	110	90-160	115
DEPTH INTERVAL (ft.)		[3.0-3.5]					
CATEGORY	Y <sub>d</sub> (pcf)	108.5	107.8	107.4	112.0	107.8 ~ 112.0	108.9
	M/C (%)	7.6	6.8	5.9	6.0	5.9-7.6	6.6
	AVERAGE q <sub>c</sub> (tsf)	250	105	80	125	80-250	140

#### EXPLANATION

Y<sub>d</sub> DRY DENSITY  
M/C MOISTURE CONTENT  
q<sub>c</sub> CONE END BEARING RESISTANCE

FIELD TEST RESULTS  
TEST TRACK C, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMO

TABLE  
3-2

**FUGRO NATIONAL, INC.**


#### 4.0 LABORATORY INVESTIGATION

Laboratory tests were performed on soil samples obtained from the test pits excavated in test tracks B and C during the first phase of field investigation. The tests consisted of: classification, compaction, relative density, CBR, and triaxial compression. The number of tests performed is summarized below:

TEST	NUMBER OF TESTS	
	Test Track B	Test Track C
Sieve Analysis	8	11
Atterberg Limits	10	1
Specific Gravity	5	3
Compaction	3	2
Relative Density	3	3
CBR	4	2
Triaxial Compression	2	1

The test procedures generally conformed to those of the American Society for Testing and Materials (ASTM) standards. In the relative density tests, both dry and wet methods were used to determine the maximum and minimum dry densities. In the CBR tests, the samples were compacted at both field and optimum moisture contents. However, only the samples compacted at optimum moisture content were soaked before performing the penetration tests. In the triaxial compression tests, the samples compacted at both field and optimum moisture contents to different densities were used.

The grain size distribution curves of soil samples from track B are shown in Figure 4-1. The results of relative density, CBR, and triaxial compression tests are presented in Table 4-1 and Figures 4-2 through 4-4, respectively.



MAXIMUM DRY DENSITY, pcf				MINIMUM DRY DENSITY, pcf	
WET METHOD		DRY METHOD		DRY METHOD	
RANGE	AVERAGE	RANGE	AVERAGE	RANGE	AVERAGE
100.0 ~ 128.6	117.6 (5)	112.6 ~ 120.4	115.9 (6)	91.4 ~ 101.1	96.0 (9)
COMPOSITE AVERAGE = 116.7					

NOTES: 1. THE ABOVE DATA IS OBTAINED FROM 3 TYPICAL SAMPLES: B-P-4 (B-1)

B-P-6 (B-1)

B-P-7 (B-1)


2. THE NUMBERS IN PARENTHESES REPRESENT THE  
NUMBER OF TESTS.

RELATIVE DENSITY RESULTS  
TEST TRACK B, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

WX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMO

TABLE  
4-1

**FUGRO NATIONAL, INC.**



SYMBOL	SAMPLE NUMBER	MOISTURE CONTENT AS TESTED (%)
○	B-P-4 (B-1)	OPTIMUM
□	B-P-7 (B-1)	OPTIMUM


CALIFORNIA BEARING RATIO (CBR) CURVE  
SOAKED TESTS, TEST TRACK B  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - DMO

FIGURE  
4-2

**FUGRO NATIONAL, INC.**

USA F-07



SYMBOL	SAMPLE NUMBER	MOISTURE CONTENT AS TESTED (%)
○	B-P-4 (B-1)	2.4, 2.2
●	B-P-4 (B-1)	5.0, 5.2
△	B-P-6 (B-1)	4.8, 4.9, 5.0
□	B-P-7 (B-1)	6.0, 6.1
■	B-P-8 (B-1)	2.9, 2.9, 2.8



CALIFORNIA BEARING RATIO (CBR) CURVE  
UNSOAKED TESTS. TEST TRACK B  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

WX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE BMO

FIGURE  
4-3

**FUGRO NATIONAL, INC.**





#### EXPLANATION

- SPECIMEN WITH OPTIMUM MOISTURE CONTENT
- SPECIMEN WITH 3% MOISTURE CONTENT

TRIAXIAL COMPRESSION TEST RESULTS  
TEST TRACK B, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

WX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMO

FIGURE  
4-4

**FLUORO NATIONAL, INC.**

The grain size distribution curves of soil samples from track C are shown in Figure 4-5. The results of relative density, CBR, and triaxial compression tests are presented in Table 4-2 and Figures 4-5 through 4-8, respectively.

Detailed laboratory test results are presented in Appendix C.



MAXIMUM DRY DENSITY, pcf				MINIMUM DRY DENSITY, pcf	
WET METHOD		DRY METHOD		DRY METHOD	
RANGE	AVERAGE	RANGE	AVERAGE	RANGE	AVERAGE
99.3 ~ 111.1	107.2 (6)	103.4 ~ 115.3	109.4 (17)	84.3 ~ 98.4	90.1 (12)
COMPOSITE AVERAGE = 108.8					

NOTES: 1. THE ABOVE DATA IS OBTAINED FROM 3 TYPICAL SAMPLES: C-P-1 (B-1)  
C-P-2 (B-1)  
C-P-3 (B-1)


2. THE NUMBERS IN PARENTHESES REPRESENT THE  
NUMBER OF TESTS.

RELATIVE DENSITY RESULTS  
TEST TRACK C, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMO

TABLE  
4-2

**FUGRO NATIONAL, INC.**



SYMBOL	SAMPLE NUMBER	MOISTURE CONTENT AS TESTED (%)
O	C-P-3 (B-3)	OPTIMUM


CALIFORNIA BEARING RATIO (CBR) CURVE  
SOAKED TESTS. TEST TRACK C  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMD

FIGURE  
4-6

**FUGRO NATIONAL, INC.**

USAF-07



SYMBOL	SAMPLE NUMBER	MOISTURE CONTENT AS TESTED (%)
○	C-P-1 (B-1)	5.2, 5.3, 5.2
□	C-P-1 (B-1)	6.8, 6.8, 6.9
●	C-P-3 (B-1)	5.4, 5.6, 5.0
■	C-P-3 (B-1)	6.6, 6.8, 6.7



CALIFORNIA BEARING RATIO (CBR) CURVE  
UNSOAKED TESTS, TEST TRACK C  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMD

FIGURE  
4-7

**UGRO NATIONAL, INC.**

USA F-07



#### EXPLANATION

- SPECIMEN WITH OPTIMUM MOISTURE CONTENT
- SPECIMEN WITH 5% MOISTURE CONTENT

TRIAXIAL COMPRESSION TEST RESULTS  
TEST TRACK C, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMO

FIGURE  
4-8

**FUGRO NATIONAL, INC.**

## 5.0 DISCUSSION OF RESULTS

In this section, the results of both the field and laboratory investigations are discussed briefly.

### 5.1 TEST TRACK B

The test pits revealed that between grade and the depths of 2.0 to 5.4 feet, the soil is a fine to coarse gravelly sand, red-brown in color, poorly to well-graded, calcareous and contains traces of nonplastic silt, fine gravel, cobbles or boulders. The sieve analysis indicates that the soils are in the SP-SM and SW-SM categories of the Unified Soil Classification System (USCS). All Atterberg limit tests performed classify the soil as nonplastic. This sand is generally dense except at test pits B-P-4 and B-P-8 where it is loose. Stage I and III caliche, with local occurrences of stage IV caliche, exist in this sand sometimes throughout or in the form of layers. This caliche changes the in situ consistency of the sand to a very dense state.

In situ dry densities of uncemented soils at track B ranged from 93.7 to 115.9 pcf. There does not seem to be any obvious trend of increasing density with depth. The limited test results of the in situ moisture contents show that the soils are drier at a greater depth, with 4.7 to 8.0 percent moisture content near the surface decreasing to about two percent at a depth of 3.5 feet. The high moisture content at the surface is due to the rainfall prior to the field work.



Results of the laboratory tests were used to estimate the CBR and angle of internal friction ( $\phi$ ) for the soils at track B at their in situ densities (see Table 5-1). The soaked CBR ranged from zero to 46 percent and the unsoaked CBR ranged from zero to 70 percent. The wide range of relative compaction of the in situ soils leads to these extreme values of CBR. The estimated angle of internal friction ( $\phi$ ) ranged from 35.3° to 40.5° at optimum moisture content and from 38.5° to 47.5° at field moisture contents.

It is difficult to interpret the CPT results of test track B because of the nonuniform distribution of the caliche cementation. The depth where the CPT met refusal varies from 0.8 to 10.8 feet (see profile in Figure 3-1). Appendix B presents detailed CPT results for track B.

## 5.2 TEST TRACK C

Between grade and the depth of 3.0 to 5.0 feet, as indicated by the test pits, the soil is a fine to medium sand, brown in color, poorly graded, and calcareous, with traces of nonplastic silt or gravel. The sieve analyses indicate that the soils are in the SP-SM and SW-SM categories of the USCS. The sand is generally medium dense and is underlain by a cemented caliche horizon which could not be excavated by a backhoe.

In situ densities of soils at track C ranged from 97.9 to 112.0 pcf. The limited test results of the in situ moisture contents show that the soils are slightly more moist at depth,

DEPTH INTERVAL (ft)	RANGE OF IN-SITU DRY DENSITY (pcf)	RANGE OF IN-SITU MOISTURE CONTENT (%)	(A) AVERAGE MAXIMUM DRY DENSITY	(B) AVERAGE MAXIMUM AND MINIMUM DRY DENSITY		RANGE OF RELATIVE COMPACTION (%)	RANGE OF RELATIVE DENSITY (%)	(C) RANGE OF ESTIMATED LAB CBR (%)		(D) RANGE OF ESTIMATED ANGLE OF INTERNAL FRICTION ( $\phi^\circ$ )	
				MAX	MIN			SOAKED	UNSOAKED	OMC	FIELD M/C
1.0-1.5	99.9~115.9	4.7~8.0	123.0	116.7	96.0	81~94	22~97	0~46	0~70	35.5~40.5	38.8~47.5
2.0-2.5	93.7~104.8	3.0~3.2	117.2	116.7	96.0	80~89	47	0~19	0~30	35.3~38.1	38.5~42.5
3.0-3.5	112.1	2.0	—	116.7	96.0	—	81	—	—	—	—
OVERALL RANGE	93.7~115.9	2.0~8.0	117.2~123.0	116.7	96.0	80~94	22~97	0~46	0~70	35.3~40.5	38.5~47.5

NOTES: (A) FROM LABORATORY COMPACTION TESTS.

(B) FROM LABORATORY RELATIVE DENSITY TESTS.

(C) FROM FIGURES 4-2 AND 4-3.

(D) FROM FIGURE 4-4.

OMC—OPTIMUM MOISTURE CONTENT.

FIELD M/C—FIELD MOISTURE CONTENT.

ESTIMATED CBR AND  $\phi$ ,  
TEST TRACK B, ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMO

TABLE  
5-1

**FUGRO NATIONAL, INC.**

with 4.9 to 5.8 percent moisture content near the surface increasing to 5.9 to 7.6 percent at a depth of 3.0 to 3.5 feet.

Results of laboratory tests were used to estimate the CBR and angle of internal friction ( $\phi$ ) for the soils at track C at their in situ densities (see Table 5-2). The soaked CBR ranged from 12 to 74 percent and the unsoaked CBR ranged from 18 to 64 percent. The estimated angle of internal friction ( $\phi$ ) ranged from  $31.5^\circ$  to  $41.0^\circ$  at optimum moisture content and from  $33.0^\circ$  to  $42.5^\circ$  at field moisture contents.

A large number of the pre-mobility test  $q_c$  (end bearing resistance, tsf) profiles from the CPTs show a steady increase of  $q_c$  in the overlying sand to about mid-depth of the total penetration. Then  $q_c$  decreases with depth until refusal at the end of the tests when the cone encountered the underlying layer of caliche; see Drawing B-1 in Appendix B. During the week of 4 August 1980, the Terex 33-15 vehicle, equipped with 50/42T tires inflated to 95 psi pressure (wheel load: 65 kips, 30 percent tire deflection, 19" x 42" footprint), traversed the test track at 10 mph for 25 successful passes. On the third day of mobility testing during the 26th pass, the vehicle got stuck near Station 6+00. The tires sank about 10 inches and the undercarriage of the vehicle (7-1/2" clearance above the ground) started dragging. Before getting stuck, the wheels were churning and even applying full throttle (1600 hp engine) did not alleviate the situation. Water was sprayed on the soil where the

DEPTH INTERVAL (ft)	RANGE OF IN SITU DRY DENSITY (pcf)	RANGE OF IN SITU MOISTURE CONTENT (%)	(A) AVERAGE MAXIMUM AND MINIMUM DRY DENSITY (pcf)	(B) AVERAGE MAXIMUM AND MINIMUM DRY DENSITY (pcf)		RANGE OF RELATIVE COMPACTION (%)	RANGE OF RELATIVE DENSITY (%)	(C) RANGE OF ESTIMATED LAB CBR (%)		(D) RANGE OF ESTIMATED ANGLE OF INTERNAL FRICTION ( $\phi^\circ$ )	
				MAX	MIN			SOAKED	UNSOAKED	OMC	FIELD M/C
1.0-1.5	97.9~110.2	4.9~5.8	108.7	108.8	90.1	90~101	46~106	12~62	18~57	R.C. 36.0~40.5 R.D. 31.5~40.5	R.C. 36.5~42.5 R.D. 33.0~42.0
2.0-2.5	100.0~108.4	5.7~6.7	108.7	108.8	90.1	92~100	58~98	15~54	26~53	R.C. 36.5~40.5 R.D. 35.0~40.0	R.C. 38.5~42.5 R.D. 36.5~42.0
3.0-3.5	107.8~112.0	5.9~7.6	108.7	108.8	90.1	99~103	96~114	48~76	50~64	R.C. 40.0~41.0 R.D. 39.5	R.C. 42.0~42.5 R.D. 41.5
OVERALL RANGE	97.9~112.0	4.9~7.6	108.7	108.8	90.1	90~103	46~114	12~76	18~64	31.5~41.0	33.0~42.5

NOTES: (A) FROM LABORATORY COMPACTION TESTS.  
 (B) FROM LABORATORY RELATIVE DENSITY TESTS.  
 (C) FROM FIGURES 4-6 AND 4-7.  
 (D) FROM FIGURE 4-8.  
 OMC - OPTIMUM MOISTURE CONTENT.  
 FIELD M/C - FIELD MOISTURE CONTENT.  
 R.C.-FROM RELATIVE COMPACTION VS.  $\phi$   
 R.D.-FROM RELATIVE DENSITY VS.  $\phi$

ESTIMATED CBR AND  $\phi$   
 TEST TRACK C, ETB MOBILITY STUDY  
 NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
 DEPARTMENT OF THE AIR FORCE - BMO

TABLE  
 5-2

**FUGRO NATIONAL, INC.**

tires sank and using a dozer, forklift, and other equipment, the Terex 33-15 was pulled out.

Post-mobility test CPTs were conducted at test track C on 15 and 16 August 1980. Some of these CPTs were performed in the rut formed by the 25 passes of the Terex vehicle. The locations of all pre- and post-mobility test CPTs are shown in Figure 3-2. Appendix B includes results of all initial and post-mobility test CPTs (end-bearing resistance versus depth only). In addition, Table 5-3 presents a numerical comparison of end-bearing resistance before and after mobility testing at depths of 1, 2, and 3 feet.

The post-mobility test CPTs on centerline and 10 feet right of centerline generally indicate an increase in cone resistance at all depths. (At 1-foot depth,  $q_c$  increased by 1 to 180 tsf, average being 40 tsf). This increase may be due to a combination of dessication and compaction by the Terex vehicle. The cone resistance decreased somewhat at Stations 6+00 and 7+00, and this decrease was likely caused by disturbance during removal of the stuck Terex vehicle.

The CPTs performed in the left tire tread mark (C-14P through C-25P, and C-38P) indicate an increase in cone resistance between Stations 0+00 to 5+00 and 10+00 to 12+00 and a decrease in cone resistance (at 1 foot depth, range of decrease = 6 to 96 tsf, average = 34 tsf) for the intermediate Stations (6+00 to 9+00). The area of decrease in cone resistance corresponds with the area of visual disturbance by the Terex 33-15 as

CPT NUMBER	CPT LOCATION	DEPTH (ft)	(1) $q_c$ (tsf)	CPT NUMBER (POST MOBILITY TEST)	CPT LOCATION	DEPTH (ft)	(2) $q_c$ (tsf)	(1-2) $\Delta q_c$ (tsf)	REMARKS	CPT NUMBER	LO
C-1	STA 0+00 ON C.L.	1.0	130	C-1P	STA 0+00 ON C.L.	1.0	151	+21	C-1P HEAVILY TRAVELED AREA NEAR 3 ROAD INTERSEC.	C-16	ST 10' L
		2.0	150			2.0	169	+19			
		3.0	115			3.0	155	+40			
C-2	STA 1+00 ON C.L.	1.0	85	C-2P	STA 1+00 ON C.L.	1.0	65	-20	C-1P THROUGH C-13P NOT IN TIRE TREAD MARK	C-17	ST 10' L
		2.0	95			2.0	115	+15			
		3.0	103			3.0	142	+39			
C-3	STA 2+00 ON C.L.	1.0	80	C-3P	STA 2+00 ON C.L.	1.0	97	+17	C-3P INCREASES POSSIBLY DUE TO DESSICATION	C-18	ST 10' L
		2.0	110			2.0	145	+35			
		3.0	105			3.0	139	+34			
C-4	STA 3+00 ON C.L.	1.0	80	C-4P	STA 3+00 ON C.L.	1.0	91	+11	C-4P SURFACE DRY AND DENSE	C-19	ST 10' L
		2.0	118			2.0	145	+27			
		3.0	175			3.0	162	-13			
C-5	STA 4+00 ON C.L.	1.0	83	C-5P	STA 4+00 ON C.L.	1.0	70	-13	C-5P SURFACE DRY AND DENSE	C-20	ST 10' L
		2.0	73			2.0	95	+22			
		3.0	84			3.0	116	+32			
C-6	STA 5+00 ON C.L.	1.0	108	C-6P	STA 5+00 ON C.L.	1.0	146	+38	C-6P SURFACE DRY AND DENSE	C-21	ST 10' L
		2.0	100			2.0	130	+30			
		3.0	72			3.0	104	+32			
C-7	STA 6+00 ON C.L.	1.0	140	C-7P	STA 6+00 ON C.L.	1.0	95	-45	C-7P NEAR AREA WHERE TEREX GOT STUCK, SURFACE DISTURBED	C-22	ST 10' L
		2.0	200			2.0	80	-120			
		3.0	110			3.0	135	+25			
C-8	STA 7+00 ON C.L.	1.0	56	C-8P	STA 7+00 ON C.L.	1.0	109	+53		C-23	ST 10' L
		2.0	240			2.0	271	+31			
		3.0	215			3.0	222	+7			
C-9	STA 8+00 ON C.L.	1.0	76	C-9P	STA 8+00 ON C.L.	1.0	113	+37		C-24	ST 10' L
		2.0	245			2.0	251	+6			
		3.0	355			3.0	321	-34			
C-10	STA 9+00 ON C.L.	1.0	68	C-10P	STA 9+00 ON C.L.	1.0	108	+38		C-25	ST 10' L
		2.0	245			2.0	257	+12			
		3.0	200			3.0	213	+3			
C-11	STA 10+00 ON C.L.	1.0	100	C-11P	STA 10+00 ON C.L.	1.0	165	+65		C-26	ST 10' L
		2.0	114			2.0	161	+27			
		3.0	95			3.0	146	+51			
C-12	STA 11+00 ON C.L.	1.0	105	C-12P	STA 11+00 ON C.L.	1.0	117	+12		C-27	ST 10' L
		2.0	105			2.0	118	+13			
		3.0	101			3.0	87	14			
C-13	STA 12+00 ON C.L.	1.0	105	C-13P	STA 12+00 ON C.L.	1.0	138	+33		C-28	ST 10' L
		2.0	90			2.0	97	+7			
		3.0	80			3.0	79	-1			
C-14	STA 12+00 10' LT OF C.L.	1.0	76	C-14P	STA 12+00 9' LT OF C.L.	1.0	70	-6	C-14P CENTER OF TIRE TREAD MARK	C-29	ST 10' L
		2.0	85			2.0	130	+45			
		3.0	7			3.0	133	+68			
C-15	STA 11+00 10' LT OF C.L.	1.0	105	C-15P	STA 11+00 13' LT OF C.L.	1.0	81	24	C-15P INSIDE EDGE OF TIRE TREAD MARK	C-30	ST 10' L
		2.0	115			2.0	154	+39			
		3.0	173			3.0	156	17			

CPT NUMBER	CPT LOCATION	DEPTH (ft.)	(1) $q_c$ (tsf)	CPT NUMBER (POST MOBILITY TEST)	CPT LOCATION	DEPTH (ft.)	(2) $q_c$ (tsf)	(1-2) $\Delta q_c$ (tsf)	REMARKS
C-16	STA 10+00 10' LT OF C.L.	1.0	92	C-16P	STA 10+00 14.5' LT OF C.L.	1.0	95	+3	C-16P CENTER OF TIRE TREAD MARK
		2.0	95			2.0	135	+40	
		3.0	102			3.0	171	+69	
C-17	STA 9+00 10' LT OF C.L.	1.0	120	C-17P	STA 9+00 17' LT OF C.L.	1.0	95	-25	C-17P OUTSIDE EDGE OF TIRE TREAD MARK
		2.0	195			2.0	122	-73	
		3.0	155			3.0	139	-16	
C-18	STA 8+00 10' LT OF C.L.	1.0	100	C-18P	STA 8+00 13' LT OF C.L.	1.0	53	-47	C-18P INSIDE EDGE OF TIRE TREAD MARK
		2.0	180			2.0	155	-25	
		3.0	170			3.0	215	+45	
C-19	STA 7+00 10' LT OF C.L.	1.0	105	C-19P	STA 7+00 14' LT OF C.L.	1.0	64	-41	C-19P CENTER OF TIRE TREAD MARK
		2.0	175			2.0	164	-11	
		3.0	155			3.0	152	-3	
C-20	STA 6+00 10' LT OF C.L.	1.0	115	C-20P	STA 6+00 16' LT OF C.L.	1.0	19	-96	C-20P OUTSIDE EDGE OF TIRE TREAD MARK
		2.0	165			2.0	65	-100	
		3.0	116			3.0	39	-77	
C-21	STA 5+00 10' LT OF C.L.	1.0	55	C-21P	STA 5+00 12' LT OF C.L.	1.0	56	+1	C-21P INSIDE EDGE OF TIRE TREAD MARK
		2.0	85			2.0	122	+37	
		3.0	80			3.0	146	+66	
C-22	STA 4+00 10' LT OF C.L.	1.0	75	C-22P	STA 4+00 12' LT OF C.L.	1.0	85	+10	C-22P CENTER OF TIRE TREAD MARK
		2.0	97			2.0	157	+65	
		3.0	99			3.0	190	+91	
C-23	STA 3+00 10' LT OF C.L.	1.0	82	C-23P	STA 3+00 14' LT OF C.L.	1.0	110	+28	C-23P OUTSIDE EDGE OF TIRE TREAD MARK
		2.0	113			2.0	200	+87	
		3.0	138			3.0	185	+47	
C-24	STA 2+00 10' LT OF C.L.	1.0	80	C-24P	STA 2+00 13' LT OF C.L.	1.0	90	+10	C-24P INSIDE EDGE OF TIRE TREAD MARK
		2.0	110			2.0	190	+80	
		3.0	123			3.0	195	+72	
C-25	STA 1+00 10' LT OF C.L.	1.0	70	C-25P	STA 1+00 15' LT OF C.L.	1.0	75	+5	C-25P OUTSIDE EDGE OF TIRE TREAD MARK
		2.0	92			2.0	156	+64	
		3.0	71			3.0	0	+99	
C-26	STA 1+00 10' RT OF C.L.	1.0	70	C-26P	STA 1+00 10' RT OF C.L.	1.0	85	+15	C-26P THROUGH C-37P NOT IN TIRE TREAD MARK
		2.0	90			2.0	103	+13	
		3.0	104			3.0	170	+66	
C-27	STA 2+00 10' RT OF C.L.	1.0	75	C-27P	STA 2+00 10' RT OF C.L.	1.0	48	+23	
		2.0	111			2.0	95	-16	
		3.0	95			3.0	109	+14	
C-28	STA 3+00 10' RT OF C.L.	1.0	70	C-28P	STA 3+00 10' RT OF C.L.	1.0	70	+0	
		2.0	105			2.0	142	+37	
		3.0	98			3.0	135	+37	
C-29	STA 4+00 10' RT OF C.L.	1.0	84	C-29P	STA 4+00 10' RT OF C.L.	1.0	109	+25	C-29 NOT IN TIRE TREAD MARK
		2.0	97			2.0	110	+13	
		3.0	83			3.0	96	+13	
C-30	STA 5+00 10' RT OF C.L.	1.0	100	C-30P	STA 5+00 10' RT OF C.L.	1.0	135	+35	
		2.0	118			2.0	119	+1	
		3.0	105			3.0	105	+0	

CPT NUMBER	CPT LOCATION	DEPTH (ft.)	(1) $q_c$ (tsf)
C-31	STA 6+00 10' RT OF C.L.	1.0	100
		2.0	175
		3.0	300
C-32	STA 7+00 10' RT OF C.L.	1.0	120
		2.0	155
		3.0	123
C-33	STA 8+00 10' RT OF C.L.	1.0	110
		2.0	210
		3.0	415
C-34	STA 9+00 10' RT OF C.L.	1.0	102
		2.0	195
		3.0	170
C-35	STA 10+00 10' RT OF C.L.	1.0	98
		2.0	100
		3.0	89
C-36	STA 11+00 10' RT OF C.L.	1.0	101
		2.0	105
		3.0	92
C-37	STA 12+00 10' RT OF C.L.	1.0	67
		2.0	85
		3.0	79
C-38	STA 0+00 10' LT OF C.L.	1.0	83
		2.0	90
		3.0	118
C-39	STA 0+00 10' RT OF C.L.	1.0	170
		2.0	172
		3.0	130
—	—	—	—
—	—	—	—
—	—	—	—
—	—	—	—
—	—	—	—
—	—	—	—

NOTES:

STA STATION  
RT RIGHT  
LT LEFT  
C.L. CENTER LINE

(1-2) $\Delta q_c$ (tsf)	REMARKS
+3	C-16P CENTER OF TIRE TREAD MARK
+40	
+69	
-25	C-17P OUTSIDE EDGE OF TIRE TREAD MARK
-73	
-16	
-47	C-18P INSIDE EDGE OF TIRE TREAD MARK
-25	
+45	
-41	C-19P CENTER OF TIRE TREAD MARK
-11	
-3	
-96	C-20P OUTSIDE EDGE OF TIRE TREAD MARK
-100	
-77	
+1	C-21P INSIDE EDGE OF TIRE TREAD MARK
+37	
+66	
+10	C-22P CENTER OF TIRE TREAD MARK
+65	
+91	
+28	C-23P OUTSIDE EDGE OF TIRE TREAD MARK
+87	
+47	
+10	C-24P INSIDE EDGE OF TIRE TREAD MARK
+80	
+72	
+5	C-25P OUTSIDE EDGE OF TIRE TREAD MARK
+64	
+99	
+15	C-26P THROUGH C-37P NOT IN TIRE TREAD MARK
+13	
+66	
+23	
-16	
+14	
+0	
+37	
+37	
+25	C-29 NOT IN TIRE TREAD MARK
+13	
+13	
+35	
+1	
+0	

CPT NUMBER	CPT LOCATION	DEPTH (ft)	(1) $q_c$ (tsf)	CPT NUMBER (POST MOBILITY TEST)	CPT LOCATION	DEPTH (ft)	(1) $q_c$ (tsf)	(1-2) $\Delta q_c$ (tsf)	REMARKS
C-31	STA 6+00 10' RT OF C.L.	1.0	100	C-31P	STA 6+00 10' RT OF C.L.	1.0	160	+60	
		2.0	175			2.0	175	+0	
		3.0	300			3.0	277	-23	
C-32	STA 7+00 10' RT OF C.L.	1.0	120	C-32P	STA 7+00 10' RT OF C.L.	1.0	200	+80	
		2.0	155			2.0	175	+20	
		3.0	123			3.0	196	+73	
C-33	STA 8+00 10' RT OF C.L.	1.0	110	C-33P	STA 8+00 10' RT OF C.L.	1.0	220	+110	
		2.0	210			2.0	257	+47	
		3.0	415			3.0	422	+7	
C-34	STA 9+00 10' RT OF C.L.	1.0	102	C-34P	STA 9+00 10' RT OF C.L.	1.0	180	+78	
		2.0	195			2.0	236	+41	
		3.0	170			3.0	—	—	
C-35	STA 10+00 10' RT OF C.L.	1.0	98	C-35P	STA 10+00 10' RT OF C.L.	1.0	170	+72	
		2.0	100			2.0	130	+30	
		3.0	89			3.0	95	+6	
C-36	STA 11+00 10' RT OF C.L.	1.0	101	C-36P	STA 11+00 10' RT OF C.L.	1.0	212	+11	
		2.0	105			2.0	155	+50	
		3.0	92			3.0	115	+23	
C-37	STA 12+00 10' RT OF C.L.	1.0	67	C-37P	STA 12+00 10' RT OF C.L.	1.0	40	-27	
		2.0	85			2.0	98	+13	
		3.0	79			3.0	200	+121	
C-38	STA 0+00 10' LT OF C.L.	1.0	83	C-38P	STA 0+00 12' LT OF C.L.	1.0	100	+17	C-38P INSIDE EDGE OF TIRE TREAD MARK
		2.0	90			2.0	150	+60	
		3.0	118			3.0	240	+122	
C-39	STA 0+00 10' RT OF C.L.	1.0	170	C-39P	STA 0+00 10' RT OF C.L.	1.0	250	+180	
		2.0	172			2.0	195	+23	
		3.0	130			3.0	131	+1	
—	—	—	—	C-40P	STA 6+27 4' RT OF C.L.	1.0	9	—	IN HEAVED SOIL AHEAD OF RUT WHERE TEREX STUCK
		—	—			2.0	172	—	
		—	—			3.0	310	—	
—	—	—	—	C-41P	STA 6+23.5 4' RT OF C.L.	1.0	135	—	IN BOTTOM OF RUT WHERE TEREX STUCK
		—	—			2.0	200	—	
		—	—			3.0	245	—	
—	—	—	—	C-42P	STA 6+12 4' RT OF C.L.	1.0	129	—	BEHIND DEEP RUT WHERE TEREX STUCK
		—	—			2.0	175	—	
		—	—			3.0	140	—	

NOTES:

STA STATION  
RT RIGHT  
LT LEFT  
C.L. CENTER LINE

COMPARISON OF PRE- AND POST-MOBILITY TEST CPTs  
TEST TRACK C  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE BMO

TABLE  
5-3

FUGRO NATIONAL, INC.



it sank and became stuck. The decreases tend to be more pronounced at the inner and outer edges of the tire track than at the center.

Three additional CPTs were performed in the right tire tread mark at the location where the Terex bogged down. As expected, the CPT (C-40P) in the heaved soil behind the wheel gave a very low value (8.5 tsf) at shallow depth but increased rapidly thereafter. Visually the upper 1-foot of material was severely displaced and gave the appearance of a pile of loose sand. The CPT (C-41P) at the deepest point of the rut where the Terex got stuck gave fairly high resistance values; this was probably a result of the wetting and compaction induced during removal of the stuck vehicle.

### 5.3 TEST TRACK G

No test pits were excavated at this test track by Fugro National but the surface material is fine to medium sand, brown in color, poorly graded, and calcareous, with traces of nonplastic silt and gravel. Based on the CPT results, the sand is generally medium dense and is underlain by a caliche layer at a depth of 5 to 6 feet as in track C.

Substantial quantities of water were added during the grading of track G. CPT's were performed following this grading operation. The CPT profiles at track G are very similar to those at track C, therefore, the same comments of Section 5.2. apply with regard to the shape of the  $q_c$  versus depth plot. The average

$q_c$  is 63, 93, and 109 tsf at depths of 1, 2, and 3 feet, respectively.

#### 5.4 VIRGIN DESERT

No test pits or field density tests were performed on the virgin desert, but the surface material visually classifies the same as at tracks C and G. The moisture content visually appears to be lower than at tracks C and G.

The seven CPTs performed on the virgin desert, 25 to 35 feet northeast of track G (see CPT logs in Appendix B), have similar  $q_c$  profile shapes. Typically, the end bearing resistance ( $q_c$ , tsf) steadily increased from the surface to refusal. The depth to refusal ranged from 4.4 to 6.0 feet. End bearing resistance averages 38, 60, and 85 tsf at 1, 2, and 3 feet below grade, respectively.

The CPT profiles of the virgin desert have a distinctly different shape than those of tracks C and G. The test track roadbed materials exhibit a peak cone resistance at 2 to 3 feet, then the resistance drops off before reaching the underlying caliche layer but the CPTs performed on the virgin desert did not exhibit this intermediate peak in cone resistance (see Drawing B-2 in Appendix B). This indicates that the surficial soils in tracks C and G have been compacted to a certain extent by the construction equipment used during the grading operations.

APPENDIX A  
Test Pit Logs

A1.0 METHODS OF EXCAVATION OF TEST PITS,  
SAMPLING, FIELD DENSITY AND MOISTURE CONTENT TESTS

A1.1 Excavation

Test pits were nominally 2 feet wide and ranged from 5 to 10 feet in length. The depths of pits were limited by the hard caliche cementation. The excavated material was deposited on one side at least 4 feet from the edge of the test pits in order to minimize stress loads at the edges. The excavations were backfilled with the excavated material and the ground surface was restored to a condition as conformable with the surrounding terrain as practical.

A1.2 Sampling

The following sampling procedures were generally followed.

- o Representative bulk soil samples (large and small) were obtained from different depths.
- o All large bulk samples were placed first in plastic bags and then in cloth bags. Small bulk samples were placed in small plastic bags. All sample bags of soil were tied tightly at the top to prevent spillage and tagged with the following information: project number; trench, test pit, or surficial sample number; bulk sample number; depth range in feet; Unified Soil Classification symbol; and date.

A1.3 In Situ Density and M/C

Where possible the in situ field densities and moisture contents were determined at depths of 1.0, 2.0 or 3.0 feet (0.3, 0.6, or 0.9 m). The sand cone method (ASTM 1556-64) was used for the field density determination. The Speedi-Moisture method was used to determine field moisture contents.

A2.0 EXPLANATIONS OF TEST PIT LOGS

Field density and moisture content test results are included in Appendix C, Table C-1.

All data from test pits are presented on standard Fugro National logs. Explanations of the column headings on the logs are as follows:

A. Designations - Test pits are identified as follows:

B-P-1

B - abbreviation for the test track (e.g., test track 'B')  
P - abbreviation for test pit  
1 - number of test pit

- B. Depth - Corresponds to depth below ground surface in meters and feet.
- C. Lithology - Graphic representation of the soil and rock types.
- D. USCS - Unified Soil Classification System (see Table A-1 for complete details) symbols.
- E. Soil Description - Except in cases where samples were classified based on laboratory test data, the descriptions are based on visual classification. The procedures outlined in ASTM D 2487-69, Classification of Soils for Engineering Purposes, and D 2488-69, Description of Soils (Visual-Manual Procedure) were followed. Solid lines across the column indicate known change in strata at the depth shown.

Definitions of some of the terms and criteria to describe soils and conditions encountered during the exploration follow.

Gradation : A coarse-grained soil is well graded if it has a wide range in grain size and substantial amounts of most intermediate particle sizes.

Poorly graded indicates that the soil consists predominantly of one size (uniformly graded) or has a wide range of sizes with some intermediate sizes obviously missing (gap-graded).

# UNIFIED SOIL CLASSIFICATION SYSTEM

MX SITING INVESTIGATION

DEPARTMENT OF THE AIR FORCE - BMD

## UGRO NATIONAL, INC.

TABLE

A-1

**Field Identification Procedures**  
(Excluding particles larger than 3 in. and being fractions on estimated weights)

Group Symbols	Typical Names	Information Required for Describing Soil
GW	Well graded gravels, gravel-sand mixtures, little or no fines	Give typical name. Indicate approximate percentages of sand and gravel, maximum size, angularity, surface condition, and hardness of the coarse and other particles. Descriptive information, and symbols in parentheses.
GP	Poorly graded gravels, gravel-sand mixtures, little or no fines	For undisturbed soils add information on stratification, degree of consolidation, moisture, and drainage characteristics.
GM	Silty gravels, poorly graded gravel-sand-silt mixtures	Example: Silty sand, gravelly, about 30% gravel, angular, rounded, 1-in maximum size, rounded and subangular sand, fine to coarse to fine about 15% non-plastic fines with low dry strength, well compacted and in place. Alluvial sand, (SM)
GC	Clayey gravels, poorly graded gravel-sand-silt mixtures	
SW	Well graded sands, gravelly sand, little or no fines	
SP	Poorly graded sands, gravelly sand, little or no fines	
SM	Silty sands, poorly graded sand-silt mixtures	
SC	Clayey sands, poorly graded sand-silt mixtures	

**Plasticity Chart**  
for laboratory classification of fine grained soils

**From Wagner, 1937.**

**Secondary Classifications.** Soils possessing characteristics of two groups are designated by combinations of group symbols. For example GW-GC, well graded gravel-sand mixture with clay binder.

**These procedures are to be performed on the minus No. 40 sieve size particles approximately 1/4 in. For field classification purposes, screening is not intended, simply remove by hand the coarse particles that interfere with the tests.**

**Dilatancy Reaction to Shaking.** Take a pat of soil, moist soil with a volume of about one-half cubic inch. Place the pat in the open palm of one hand and shake horizontally, striking vigorously against the other hand several times. A positive reaction consists in the pat becoming increasingly and becoming shivery. When the sample is squeezed between the fingers the water and fines disappear from the surface, the pat stiffens and finally it cracks or crumbles. The rapidity of appearance of water during shaking and of its disappearance during squeezing assist in identifying the character of the fines in a soil. Very plastic clays, when moistened, will show a moderate increase in plasticity, but they will not react. Inorganic silt, such as a typical rock flour, show a moderately quick reaction.

Moisture : Dry - no feel of moisture  
 Slightly Moist - much less than normal moisture  
 Moist - normal moisture for soil  
 Very Moist - much greater than normal moisture  
 Wet - for soils below the water table

Consistency: Consistency descriptions of coarse-grained soils (GW, GP, GM, GC, SW, SP, SM, SC) are as follows.

Consistency

Very Loose  
 Loose  
 Medium Dense  
 Dense  
 Very Dense

Grain Shape: Angular - particles have sharp edges and relatively plane sides with unpolished surfaces.

Subangular - particles are similar to angular but have somewhat rounded edges.

Subrounded - particles exhibit nearly plane sides but have well-rounded corners and edges.

Rounded - particles have smoothly curved sides and no edges.

Calcareous : Containing calcium carbonate; presence of calcium carbonate is commonly identified on the basis of reaction with dilute hydrochloric acid.

Caliche : Soils cemented by calcium carbonate and/or other soluble minerals by upward-moving solutions.

Degree of Cementation: (Stages of development of caliche profile)

Stage	<u>Gravelly Soils</u>	<u>Nongravelly Soils</u>
I	Thin, discontinuous pebble coatings	Few filaments or faint coatings

II	Continuous pebble coatings, some interpebble fillings	Few to abundant nodules, flakes, filaments
III	Many interpebble fillings	Many nodules and internodular fillings
IV	Laminar horizon overlying plugged horizon	Increasing carbonate impregnation

## Secondary

Material : Example - Sand with trace to some silt

Trace - 5-12% (by dry weight)

Little - 13-20% (by dry weight)

Some - >20% (by dry weight)

Plasticity : Plasticity index is the range of water content, expressed as a percentage of the weight of the oven-dried soil, through which the soil is plastic. It is defined as the liquid limit minus the plastic limit. Descriptive ranges used on the logs include:

Nonplastic (PI, 0 - 4)

Slightly Plastic (PI, 4 - 15)

Medium Plastic (PI, 15 - 30)

Highly Plastic (PI, >30)

## Cobbles and

Boulders : A cobble is a rock fragment, usually rounded by weathering or abrasion, with an average diameter ranging between 3 and 12 inches.

A boulder is a rock fragment, usually rounded by weathering or abrasion, with an average diameter of 12 inches or more.

I. Remarks - This column was provided on test pit logs for comments regarding number and size of cobbles or boulders encountered, trench wall stability, and other conditions encountered during excavations.

K. Sieve Analysis - The numbers represent the percentage by dry weight (ASTM D 422-63) of each of the following soil components:

GR - Gravel, rock particles that will pass a 3-inch sieve and are retained on No. 4 sieve.



SA - Sand, soil particles passing No. 4 sieve and retained on No. 200 sieve.

FI - Fines, silt or clay, soil particles passing No. 200 sieve.


L. Atterberg Limits (LL and PI) -

LL - Liquid Limit, the water content corresponding to the arbitrary limit between the liquid and plastic states of consistency of a soil (ASTM D 423-66).

PL - Plastic Limit, the water content corresponding to an arbitrary limit between the plastic and the semisolid state of consistency of a soil (ASTM D 424-59).


PI - Plasticity Index, numerical difference between the liquid limit (LL) and the plastic limit (PL) indicating the range of moisture content within which a soil-water mixture is plastic.

NP - Nonplastic.

BULK SAMPLE	DEPTH		LITHOLOGY	USCS	CONSISTENCY	SOIL DESCRIPTION	REMARKS	SIEVE ANALYSIS				
	METERS	FEET						GR	SA	FI	LL	PI
	0	0		SP-SM	dense	GRAVELLY SAND, red-brown, fine to coarse, well graded, slightly moist, subangular, calcareous; little fine gravel; trace nonplastic silt; trace cobbles and boulders to 14" size; stage I caliche (0.0-2.0); stage IV caliche (2.0-2.5').		19	69	12		NP
	1											
	2				very dense							
	3					TOTAL DEPTH 2.5' (0.8 m)						
	4											
	5											

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

#### LOG OF TEST PIT B-P-1

	0	0		SP-SM	very dense	GRAVELLY SAND, light brown to white, fine to coarse, poorly graded, slightly moist, angular to subangular, calcareous; some fine gravel; trace nonplastic silt; trace to little cobbles and boulders to 13" size; stage III-IV caliche.		26	67	7		NP
	1											
	2											
	3					TOTAL DEPTH 2.0 (0.6 m)						
	4											
	5											

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

#### LOG OF TEST PIT B-P-2

LOGS OF TEST PITS B-P-1 AND B-P-2, TEST TRACK 8  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - DMO

FIGURE  
A-1

**FUGRO NATIONAL, INC.**

USAF-38

BULK SAMPLE	DEPTH		LITHOLOGY	USCS	CONSISTENCY	SOIL DESCRIPTION	REMARKS	SIEVE ANALYSIS				
	METERS	FEET						GR	SA	FI	LL	PI
	0	0		SP-SM	dense	GRAVELLY SAND, red-brown, fine to coarse, poorly graded, slightly moist, angular to subangular, calcareous; some fine to coarse angular to subangular gravel; trace nonplastic silt; trace cobbles and boulders to 16" size; stage III caliche (2.0'-3.0').		31	60	9		NP
	1	1										
	2	2			very dense							
	3	3										
	1					TOTAL DEPTH 3.0' (0.9 m)						
	4											
	5											

SURFACE ELEVATION:

SURFICIAL GEOLOGIC UNIT:

#### LOG OF TEST PIT B-P-3

	0	0		SP-SM	loose	GRAVELLY SAND, light brown, fine to coarse, poorly to well graded, dry, angular to subangular, calcareous; some fine angular to subangular gravel; trace nonplastic silt; stage I-II caliche (0.0'-4.0'); stage II-III caliche (4.0'-4.5').		36	57	7		NP
	1	1										
	2	2										
	3	3										
	1			SW-SM				22	73	5		NP
	4	4			very dense							
	5	5				TOTAL DEPTH 4.5 (1.4 m)		26	69	5		NP

SURFACE ELEVATION:

SURFICIAL GEOLOGIC UNIT:

#### LOG OF TEST PIT B-P-4

LOGS OF TEST PITS B-P-3 AND B-P-4, TEST TRACK B  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMD

FIGURE  
A-2

**FUGRO NATIONAL, INC.**

USA F-36

BULK SAMPLE	DEPTH METERS FEET	LITHOLOGY	USCS	CONSISTENCY	SOIL DESCRIPTION	REMARKS	SIEVE ANALYSIS				
							GR	SA	FI	LL	PI
	0		SP-SM	dense	GRAVELLY SAND, red-brown to white-brown, fine to coarse, poorly graded, slightly moist, angular to subangular, calcareous; some fine angular to subangular gravel; trace nonplastic silt; occasional cobbles to 5" size; stage II caliche (0.0'-3.5'); stage II-III caliche (3.5'-4.0).		23	65	12		NP
	1										
	2										
	3										
	4			very dense							
	5				TOTAL DEPTH 4.0' (1.2 m)						

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

#### LOG OF TEST PIT B-P-5

	0		SP-SM	dense	GRAVELLY SAND, light brown-white, fine to coarse poorly graded, dry, angular, calcareous; little fine gravel; trace nonplastic silt; stage II-III caliche throughout.		20	71	9		NP
	1			very dense		cementation					
	2										
	3			dense							
	4										
	5				TOTAL DEPTH 5.0' (1.5 m)						

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

#### LOG OF TEST PIT B-P-6


LOGS OF TEST PITS B-P-5 AND B-P-6, TEST TRACK B  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA.

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMD

FIGURE  
A-3

**JUGRO NATIONAL, INC.**

USAF-36

BULK SAMPLE	DEPTH		LITHOLOGY	USCS	CONSISTENCY	SOIL DESCRIPTION	REMARKS	SIEVE ANALYSIS				
	METERS	FEET						GR	SA	FI	LL	PI
	0	0		SP-SM	dense	SAND, red-brown, fine to coarse, poorly graded, slightly moist, subangular, calcareous; trace fine angular to subangular gravel; trace nonplastic silt; stage IV caliche (2.0'-2.2').						
	1											
	2							11	79	10		NP
						TOTAL DEPTH 2.2' (0.7 m)						
	3											
	4											
	5											

SURFACE ELEVATION:

SURFICIAL GEOLOGIC UNIT:

LOG OF TEST PIT B-P-7

	0	0										
	1											
	2											
	3											
	4											
	5											

SURFACE ELEVATION:

SURFICIAL GEOLOGIC UNIT:

LOG OF TEST PIT


LOG OF TEST PIT B-P-7, TEST TRACK B  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMD

FIGURE  
A-4

**FUGRO NATIONAL, INC.**

USAF-36

BULK SAMPLE	DEPTH		LITHOLOGY	USCS	CONSISTENCY	SOIL DESCRIPTION	REMARKS	SIEVE ANALYSIS					
	METERS	FEET						GR	SA	FI	LL	PI	
	0	0				GRAVELLY SAND, red-brown to light brown-white, fine to coarse, poorly graded, slightly moist, subangular, calcareous; little fine subangular gravel; trace nonplastic silt; stage II-III caliche (4.0'-5.4').							
		1			loose			16	75	9		NP	
		2											
		3		SP-SM	very dense			strongly cemented					
		4			dense								
		5											
		6				TOTAL DEPTH 5.4' (1.6m)							
		7											
		8											
		9											
		10											

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

LOG OF TEST PIT B-P-8

LOG OF TEST PIT B-P-8, TEST TRACK B  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - DND

FIGURE  
A-5

**FUGRO NATIONAL INC.**

USAF-21

BULK SAMPLE	DEPTH METERS FEET	LITHOLOGY	USCS	CONSISTENCY	SOIL DESCRIPTION	REMARKS	SIEVE ANALYSIS				
							GR	SA	FI	LL	PI
	0				SAND, brown, fine to medium, poorly graded, slightly moist, subangular to subrounded, calcareous; trace nonplastic silt.						
	1										
	2		SP-SM	medium dense			4	89	7	NP	
	3										
	4										
	5		SP-SM	medium dense	GRAVELLY SAND, brown, fine to coarse, poorly graded, dry, subangular to subrounded, calcareous; trace to some fine to coarse subangular to subrounded gravel; trace nonplastic silt; some cobbles and boulders to unknown size (partially exposed); stage IV caliche (4.5-2.0).		13	80	7		
	6			very dense		Jack hammer used					
	7						43	52	5		
	8										
	9										
	10										
	11										
	12										
	13										
	14										
	15										
	16										
	17										
	18										
	19										
	20										
	21										
	22										
	23										
	24										
	25										
	26										
	27										
	28										
	29										
	30										
	31										
	32										
	33										
	34										
	35										
	36										
	37										
	38										
	39										
	40										
	41										
	42										
	43										
	44										
	45										
	46										
	47										
	48										
	49										
	50										
	51										
	52										
	53										
	54										
	55										
	56										
	57										
	58										
	59										
	60										
	61										
	62										
	63										
	64										
	65										
	66										
	67										
	68										
	69										
	70										
	71										
	72										
	73										
	74										
	75										
	76										
	77										
	78										
	79										
	80										
	81										
	82										
	83										
	84										
	85										
	86										
	87										
	88										
	89										
	90										
	91										
	92										
	93										
	94										
	95										
	96										
	97										
	98										
	99										
	100										

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

# LOG OF TEST PIT C-P-1



LOG OF TEST PIT C-P-1, TEST TRACK C  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - DND

FIGURE  
A-6

FUGRO NATIONAL INC.

USAF-21

BULK SAMPLE	DEPTH		LITHOLOGY	USCS	CONSISTENCY	SOIL DESCRIPTION	REMARKS	SIEVE ANALYSIS				
	METERS	FEET						GR	SA	FI	LL	PI
	0	0		SP-SM	medium dense	SAND, brown, fine to coarse, poorly graded, slightly moist, subangular to subrounded, calcareous; trace to little fine gravel; trace nonplastic silt; occasional lenses of fine to coarse subangular to subrounded gravel.						
		1										
		2						5	85	10		
		3										
	1							14	77	9		
		4		GP	very dense	SANDY GRAVEL, brown, fine to coarse, poorly graded, slightly moist, subangular to subrounded, calcareous; some fine to coarse subangular to subrounded sand; stage IV caliche (4.5'-4.7'); stage I-II caliche (4.7'-5.5').						
		5										
		6				TOTAL DEPTH 5.5' (1.7m)						
	2											
		7										
		8										
		9										
	3											
		10										

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

# LOG OF TEST PIT C-P-2

LOG OF TEST PIT C-P-2, TEST TRACK C  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - DMO

FIGURE  
A-7

**UGRO NATIONAL, INC.**

USAF-21



BULK SAMPLE	DEPTH		LITHOLOGY	USCS	CONSISTENCY	SOIL DESCRIPTION	REMARKS	SIEVE ANALYSIS				
	METERS	FEET						GR	SA	FI	LL	PI
	0	0		SP-SM	medium dense	SAND, brown, fine to medium, poorly graded, slightly moist to dry, subangular to subrounded, calcareous; trace nonplastic silt; trace fine gravel; stage <u>IV</u> caliche at 5.0'.						
	1							5	87	8		
	2							4	87	9		
	3	1										
	4							2	88	10		
	5					TOTAL DEPTH 5.0' (1.5m) .						

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

#### LOG OF TEST PIT C-P-3

	0	0																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
--	---	---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

SURFACE ELEVATION:  
SURFICIAL GEOLOGIC UNIT:

#### LOG OF TEST PIT C-P-4

LOG OF TEST PIT C-P-3 AND C-P-4, TEST TRACK C  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - BMD

FIGURE  
A-8

**UGRO NATIONAL, INC.**

USAF-38

APPENDIX B

Results of Cone Penetration Tests

## B1.0 CONE PENETRATION TEST METHOD

### B1.1 Equipment

The equipment consisted of a truck-mounted [17.5 tons gross weight] electronic cone penetrometer equipped with a 15-ton friction cone (cone end resistance capacity of 15 tons and 4-1/2-ton limit on the friction sleeve). All operating controls, recorder, cables, and ancillary equipment were housed in the specially designed vehicle which was completely self-contained. The penetrometer, the key element of the system, contained the necessary load cells and cable connections. One end of the unit was threaded to receive the first sounding rod. When carrying out the tests, hollow rods with an outside diameter of 1.42 inches and a length of 3.3 feet were used to push down the cone.

The hydraulic thrust system was mounted over the center of gravity of the truck, permitting use of the full 17.5-ton truck weight as load reaction.

The cone had an apex angle of  $60^\circ$  and a base area of 2.3 in<sup>2</sup>. The resistance to penetration was measured by a built-in load cell in the tip and was relayed to the surface recorder via cables in the sounding rods. The friction sleeve, having an area of 31.4 in<sup>2</sup>, was fitted above the cone base. The local friction was measured by load cells mounted in the friction sleeve and recorded in the same manner as the end resistance. The end resistance and friction resistance were recorded on a strip chart.

### B1.2 Test Method

Tests were performed in accordance with ASTM D3441-75T, "tentative Method for Deep, Quasi-Static, Cone and Friction-Cone Penetration Tests of Soil." Basically, the test was conducted by positioning the electronic cone penetrometer truck over the designated area for testing, setting the outriggers on the ground surface, checking the level of the rig, then pushing the cone into the ground at a rate of 0.79 in/s until refusal (defined as the capacity of the cone, friction sleeve, or hydraulics system) or the desired depth of penetration was reached.


## B2.0 CPT RESULTS


The results of all cone penetration tests are presented in Drawings B-1, and B-2. Explanations of the test results are as follows:

- A. Depth - Corresponds to depth below ground surface.
- B. Cone Resistance - The resistance to penetration developed by the cone, equal to the vertical force applied to the cone divided by its horizontally projected area.
- C. Designation - Each cone penetrometer test is identified by a number: for example C-1.

C - abbreviation for the CPT  
1 - number of the test

- D. Soil Column - A graphical presentation of the soil type versus depth at those cone penetrometer test locations where the corresponding test pits are five (5) to ten (10) feet away. The Unified Soil Classification Symbol for each different soil type is listed immediately to the left of the soil column. Immediately below the soil column, where applicable the number for the corresponding test pit at each CPT location is given.





CE

CO

600 700 800 900 (kg/cm<sup>2</sup>)  
600 700 800 900 (tsf)

SOIL  
COLUMN

DEPTH

0 (METERS) 0 (FEET)  
0 100 200 300 400  
0 100 200 300 400

C-12 A


C-13

C-14

C-15

C-16

C-17





# CONE RESISTANCE

0 200 300 400 500 600 700 800 900 (kg/cm<sup>2</sup>)  
 0 200 300 400 500 600 700 800 900 (tsf)

SOIL  
COLUMN

C-26

C-27


C-28

C-29

C-30

C-31

✓



5

0 0

1

5

2

3 10

4

15

5

0 0

1

5

2

3 10

4

15

5

0 0

1

5

2

0 0

1

5

2

0 0

1

5

2

0 0

1

C-17

C-18

C-19

C-19A


C-20

C-21

17



18



19

20

21

2

0 0

1

5

2

0 0

1

5

2

3 10

4

15

5

0 0

1

5

2

0 0

1

5

2

3 10

4

0 0

1

5


2


0 0

1

5

2





C-31

C-32

C-33


C-34

C-35



C-36

5

CHECKED BY \_\_\_\_\_ APPROVED BY \_\_\_\_\_



9



800 900 (tsf)  
800 900 (kg/cm<sup>2</sup>)

0 100 200 300 400 500 600  
0 100 200 300 400 500 600

C-21

C-22

C-23

C-24

C-25

600 700 800 900 (tsf)  
600 700 800 900 (kg/cm<sup>2</sup>)

0 0

1

5

2

3 10

4

0 0

1

5

2

0 0

1

5


2

3 10

4

0 100 200 300 400  
0 100 200 300 400





**CONE PENETROMETER TEST RESULTS,  
TEST TRACK B, ETB MOBILITY STUDY,  
NEVADA TEST SITE, NEVADA**

**MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - SAMSO**

**DRAWING**


**B-1**

**1 of 2**

**FUGRO NATIONAL, INC.**

12

CONE RESISTANCE



[illegible]

[illegible]

--

(METERS)

[illegible]

# CONE RESISTANCE

200 300 400 500 600 700 800 900 (kg/cm<sup>2</sup>)  
 200 300 400 500 600 700 800 900 (tsf)

SOIL  
COLUMN

4

1

1  
5  
2  
0 0  
1  
5  
2  
0 0  
1  
5  
2  
3 10  
4


C-44

C-45


C-46

h


[illegible]









CHECKED BY \_\_\_\_\_ APPROVED BY \_\_\_\_\_




0 100 200 300 400 500 600 700 800 900  
0 100 200 300 400 500 600 700 800 900




900 (tsf)  
900 (kg/cm<sup>2</sup>)

0 100 200 300 400 500 600 700  
0 100 200 300 400 500 600 700




700 800 900 (tsf)  
700 800 900 (kg/cm<sup>2</sup>)



0 100 200 300 400  
0 100 200 300 400

11



200 300 400 500 600 700 800 900 (tsf)  
200 300 400 500 600 700 800 900 (kg/cm<sup>2</sup>)

**CONE PENETROMETER TEST RESULTS,  
TEST TRACK B, ETB MOBILITY STUDY,  
NEVADA TEST SITE, NEVADA**

**MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - SAMSO**


**DRAWING  
B-1  
2 of 2**

**FUGRO NATIONAL, INC.**

12

# TEST TRACK C

CONE RESISTANCE



2

# CONE RESISTANCE

900 (kg/cm<sup>2</sup>)  
900 (tsf)

SOIL  
COLUMN

DEPTH

(METERS)  
(FEET)

0 100 200 300 400 500 600 700  
0 100 200 300 400 500 600 700

C-12 & C-12

C-13 & C-13

C-14 & C-14


C-15 & C-15

C-16 & C-16

# CONE RESISTANCE


700 800 900 (kg/cm<sup>2</sup>)  
700 800 900 (tsf)

SOIL  
COLUMN




DEPTH






0 (METERS) 0 (FEET)  
0 100 200 300 400 500  
0 100 200 300 400 500






	C-26	C-26P		
	C-27	C-27P		
	C-28	C-28P		









ck

C-30 & C-30P




C-31 & C-31P




C-32 & C-32P




C-33 & C-33P



C-34 & C-34P






C-35 & C-35P



4

CHECKED BY \_\_\_\_\_ APPROVED BY \_\_\_\_\_





C-21 & C-21P

C-22 & C-22P

C-23 & C-23P

C-24 & C-24P

800 700 800 900 (tsf)  
800 700 800 900 (kg/cm<sup>2</sup>)

10

0

1

2

10

0

1

2

10



0 100 200 300 400  
0 100 200 300 400

### EXPLANATION

— PRE-MOBILITY TEST CPTs  
—○— POST-MOBILITY TEST CPTs



4



SP - SM

P-3

**EXPLANATION**

- PRE-MOBILITY TEST CPTs
- POST-MOBILITY TEST CPTs


<p><b>CONE PENETROMETER TEST RESULTS</b>  <b>TEST TRACKS C,G, AND VIRGIN DESERT</b>  <b>ETB MOBILITY STUDY</b>  <b>NEVADA TEST SITE, NEVADA</b></p>	
<p>MX SITING INVESTIGATION          DEPARTMENT OF THE AIR FORCE - BMO</p>	<p>DRAWING  <b>B-2</b>          1 of 2</p>

**FUGRO NATIONAL, INC.**

12

# TEST TRACK C CONTINUED

CONE RESISTANCE



CONE RESISTANCE

DEPTH

0 (METERS)  
0 (FEET)



0 100 200 300 400 500 600  
0 100 200 300 400 500 600

800 900 (kg/cm<sup>2</sup>)  
800 900 (tsf)

SOIL  
COLUMN

SP-SM

P-1



RESISTANCE


500 600 700 800 900 (kg/cm<sup>2</sup>)  
500 600 700 800 900 (tsf)

SOIL  
COLUMN

		C-10			
		C-11			
		C-12			
		C-13			
		C-14			
		C-15			

DEPTH

(METERS) 0 1 2  
(FEET) 0 100 200 300




# CONE RESISTANCE


100 200 300 400 500 600 700 800 900 (kg/cm<sup>2</sup>)  
 100 200 300 400 500 600 700 800 900 (tsf)

SOIL  
COLUMN


C-7




5





TEST TRACK G






VIRGIN DESERT












8


CHECKED BY \_\_\_\_\_ APPROVED BY \_\_\_\_\_






900 (tsf)  
900 (kg/cm<sup>2</sup>)

0 100 200 300 400 500 600 700  
0 100 200 300 400 500 600 700




600      700      800      900      (tsf)  
 800      700      800      900      (kg/cm<sup>2</sup>)



0      100      200      300      400  
 0      100      200      300      400

### EXPLANATION

- PRE-MOBILITY TEST CPTS
- o-o- POST MOBILITY TEST CPTS



200 300 400 500 600 700 800 900 (tsf)  
200 300 400 500 600 700 800 900 (kg/cm<sup>2</sup>)

**EXPLANATION**

- PRE-MOBILITY TEST CPTS
- POST MOBILITY TEST CPTS

<b>CONE PENETROMETER TEST RESULTS TEST TRACKS C,G, AND VIRGIN DESERT ETB MOBILITY STUDY NEVADA TEST SITE, NEVADA</b>	
<b>MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE -BMO</b>	<b>DRAWING B-2 2072</b>
<b>FUGRO NATIONAL, INC.</b>	

12

APPENDIX C  
Results of Laboratory Tests

C1.0 EXPLANATIONS OF LABORATORY TEST  
METHODS AND RESULTS

Laboratory test results are presented in this section. Table C-1 contains a summary of laboratory test results. This table contains results of sieve analysis; plasticity data; in-situ dry unit weight, moisture content, results of compaction tests; and specific gravity of solids. Other tests such as triaxial compression and California Bearing Ratio (CBR) are indicated on the table. Tables C-2 through C-5 present results of triaxial compression and CBR tests.

All tests were performed in general accordance with the American Society for Testing and Materials (ASTM) procedures. The following list presents the ASTM designations for the tests performed during the investigation.

<u>Type of Test</u>	<u>ASTM Designations</u>
Particle Size Analysis	D 422-63
Liquid Limit	D 423-66
Plastic Limit	D 424-59
Moisture Content	D 2216-71
Compaction	D 1557-70
Relative Density	D 2049-69
Specific Gravity of Solids	D 854-58
Triaxial Compression	D 2850-70
California Bearing Ratio (CBR)	D 1883-73

Explanation for the tables and figures presented in this section are as follows.

- A. Test pit Number - Test pit designation.
- B. Sample Number - Prefix indicates the type of sample; explanation is at the bottom of the table.
- C. Sample Interval - This is the depth range measured from ground surface over which the sample was obtained.

- D. Percent Finer by Weight - Presents the results of laboratory particle size analysis (ASTM D 422-63) performed on representative soil samples at the depth indicated. The numbers represent the percent (by dry weight) of the total sample weight passing through each sieve size indicated.
- E. Atterberg Limits (ASTM D 423-66 and D 424-59)
- LL - Liquid Limit, the water content (as percent of soil dry weight) corresponding to the arbitrary limit between the liquid and plastic states of consistency of a soil (ASTM D 423-66).
- PL - Plastic Limit, the water content corresponding to an arbitrary limit between the plastic and the semisolid state of consistency of a soil (ASTM D 424-59).
- PI - Plasticity Index, numerical difference between the liquid limit (LL) and the plastic limit (PL) indicating the range of moisture content within which a soil-water mixture is plastic.
- NP - Nonplastic.
- F. USCS - Unified Soil Classification Symbols are given here; see Table A-1 in Appendix A for complete details of USCS system.
- G. In Situ - Presents results of field density and moisture content tests.
- Dry Unit Weight - indicates dry unit weight of soil determined as per sand cone method (ASTM D 1556-64)
- Moisture Content - weight of water reported in percent of dry weight of soil sample
- H. Compacted - Indicates results of laboratory maximum dry density and optimum moisture content test as per ASTM D 1557-70.
- I. Specific Gravity of Solids (ASTM D 854-58) - Indicates the ratio of (1) the weight in air of a given volume of soil solids at a stated temperature, to (2) the weight in air of an equal volume of distilled water at a stated temperature.
- J. Triaxial - The triaxial compression tests were performed in accordance with the procedures of ASTM D 2850-70. The following explanations and definitions apply.



Triaxial Compression Test - a cylindrical specimen of soil is surrounded by a fluid in a pressure chamber and subjected to an isotropic pressure. An additional compressive load is then applied, directed along the axis of the specimen called the axial load.

Consolidated-Drained (CD) Test - a triaxial compression test in which the soil was first consolidated under an all-around confining stress (test chamber pressure), and was then compressed (and hence sheared) by increasing the vertical stress. "Drained" indicates that excess pore water pressure generated by strains are permitted to dissipate by the free movement of pore water during consolidation and compression.

Consolidated-Undrained (CU) Test - a triaxial compression test in which essentially complete consolidation under the confining (chamber) pressure is followed by a shear test at constant water content.

Confining Pressure ( $G_3$ ) - the isotropic chamber pressure applied to the soil specimen during consolidation and compression.

Maximum Deviator Stress ( $G_1 - G_3$ ) - the difference between the major and minor principal stresses in the specimen at failure. The major principal stress on the specimen is equal to the unit axial load plus the chamber pressure and the minor principal stress on the specimen is equal to the chamber pressure.

Strain Rate - axial strain,  $E$ , at a given stress level is defined as the ratio of the change in length ( $L$ ) of the specimen to the original length of the specimen ( $L_0$ ). The rate of strain was controlled during the test so that this ratio increased at equal increments for each minute of testing.

Back Pressure - pressure in excess of atmospheric applied to the pore water of a soil sample. Back pressure is usually applied to (1) increase saturation of the sample, or (2) simulate the actual in-situ pressure regime.

- K. CBR - California Bearing Ratio (CBR) is the ratio (in percent) of the resistance to penetration developed by a subgrade soil to that developed by a standard crushed-rock base material. The procedures for conducting a CBR test were as outlined in ASTM D 1883-73. The materials tested for CBR were also analyzed for particle size distribution (ASTM D 422-63) and compaction characteristics (ASTM D 1557-70), as well as relative density (ASTM D 2049-69). The term "percentage of maximum density" indicates the ratio (as a percentage) of the dry unit weight of the compacted sample to maximum dry density obtained in the laboratory

from ASTM D 1557-70, "Moisture-Density Relations of Soils Using 10-pound Hammer and 18-inch Drop."

- L. Relative Density (R.D.)- indicates the state of denseness of a soil and is defined by:

$$R.D. = \frac{\gamma_d \text{ maximum} (\gamma_d - \gamma_d \text{ minimum}) \times 100\%}{\gamma_d (\gamma_d \text{ maximum} - \gamma_d \text{ minimum})}$$

where  $\gamma_d$  maximum,  $\gamma_d$  minimum and  $\gamma_d$  are the dry densities of the soil as determined in the laboratory per ASTM method of test D-2049-69.



SEPARATION BY WEIGHT								ATTERBERG LIMITS (b)			USCS (c)	IN-SITU					COMPACTED				SPECIFIC GRAVITY
U S STANDARD SIEVE NO					PARTICLE SIZE (mm)							DRY UNIT WEIGHT		MOISTURE CONTENT (%)	SATURATION (%)	VOID RATIO	MAXIMUM DRY DENSITY		OPTIMUM MOISTURE (%)		
SAND				SILT OR CLAY			(pcf)					(kg/m <sup>3</sup> )	(pcf)				(kg/m <sup>3</sup> )				
NO	4	10	40	100	200	.005	.001	LL	PL	PI											
2	81	71	53	20	12					NP	SW-SM	115.9	1857	8.0						2.66	
4	74	67	53	15	7					NP	SP-SM										
6	69	59	40	17	9					NP	SP-SM	113.5	1818	7.0						2.61	
8	64	51	34	14	7					NP	SP-SM	105.2	1685	4.8			122.8	1967	10.0	2.64	
10	78	61	29	10	5					NP	SP-SM	104.8	1679	3.0							
15	74	47	19	3	5					NP	SW-SM	112.1	1796	2.0							
20	77	67	48	20	12					NP	SP-SM	114.5	1834	7.0							
30	80	72	52	16	9					NP	SP-SM	93.7	1501	3.2			117.2	1878	12.0	2.63	
40	89	81	61	21	10					NP	SP-SM	109.6	1757	5.4			123.1	1972	10.8		
60	84	74	59	17	9					NP	SP-SM	99.9	1600	4.7						2.60	
80																					
9	96	93	82	23	7					NP	SP-SM	110.2	1765	4.9			107.3	1719	12.0	2.61	
5	87	77	56	13	7						SP-SM	108.5	1738	7.0							
0	57	47	25	8	5						SP-SM										
8	55	42	24	10							SP-SM	105.0	1682	5.0						2.61	
4	86	77	59	19	9						SP-SM	107.8	1727	6.8							
8	95	90	74	19	8						SP-SM	108.5	1738	5.6			111.0	1778	12.5		
8	96	92	79	23	9						SP-SM	100.0	1602	6.1							
00	98	95	83	27	10						SP-SM	107.4	1721	5.9							
8	94	88	76	25	11						SP-SM	97.9	1568	5.8							
7	91	86	70	23	10						SP-SM	104.8	1679	6.3							
1	80	68	49	12	6						SW-SM	112.0	1794	6.0						2.61	
										</											

[illegible]

TEST PLT NO.	SAMPLE NO.	SAMPLE INTERVAL		SOIL TYPE	TYPE OF TEST	DRY DENSITY		MOISTURE CONTENT (%)	CONFINING PRESSURE (σ <sub>3</sub> )		MAXIMUM DEVIATOR STRESS (σ <sub>1</sub> -σ <sub>3</sub> )		STRAIN RATE (% min)	BACK PRESSURE	
		FEET	METERS			pcf	kg/m <sup>3</sup>		ksf	kn/m <sup>2</sup>	ksf	kn/m <sup>2</sup>		ksf	kn/m <sup>2</sup>
B-P-4	B-1	1.0-2.0	0.30-0.61	SP-SM	CD	117.7	1886	10.3	0.6	29	7.1	340	0.08	0	0
				SP-SM	CD	118.7	1902	10.0	1.2	57	10.4	498	0.08	0	0
				SP-SM	CD	118.7	1902	10.1	2.3	110	18.0	862	0.10	0	0
				SP-SM	CD	118.5	1898	9.7	4.6	220	30.7	1470	0.10	0	0
				SP-SM	CD	110.7	1773	10.0	0.6	29	3.4	163	0.08	0	0
				SP-SM	CD	110.6	1772	10.1	1.2	57	6.0	287	0.10	0	0
				SP-SM	CD	110.8	1775	10.3	2.3	110	10.4	498	0.08	0	0
				SP-SM	CD	111.0	1778	9.8	4.6	220	16.6	795	0.08	0	0
				SP-SM	CD	98.0	1570	11.7	0.6	29	2.4	115	0.10	0	0
				SP-SM	CD	98.2	1573	10.2	1.2	57	3.7	177	0.08	0	0
				SP-SM	CD	97.9	1568	10.5	2.3	110	6.8	326	0.09	0	0
				SP-SM	CD	97.4	1560	11.0	4.6	220	14.0	670	0.10	0	0
				SP-SM	CD	119.6	1916	2.8	0.6	29	9.4	450	0.08	0	0
				SP-SM	CD	119.3	1911	2.9	1.2	57	12.8	613	0.08	0	0
				SP-SM	CD	119.6	1916	2.9	2.3	110	17.1	819	0.08	0	0
				SP-SM	CD	119.1	1908	3.1	4.6	220	31.7	1518	0.08	0	0
				SP-SM	CD	112.6	1804	2.8	0.6	29	4.5	215	0.09	0	0
				SP-SM	CD	112.5	1802	3.1	1.2	57	7.5	359	0.09	0	0
				SP-SM	CD	112.6	1804	2.9	2.3	110	12.9	618	0.09	0	0
				SP-SM	CD	112.5	1802	3.1	4.6	220	22.6	1082	0.09	0	0

SUMMARY OF TRIAXIAL COMPRESSION  
TEST RESULTS, TEST TRACK R ETB MOBILITY  
STUDY, NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE BMO

TABLE  
C-2  
1 of 2

FUSRO NATIONAL INC.

AFV-10

TEST PIT NO.	SAMPLE NO.	SAMPLE INTERVAL		SOIL TYPE	TYPE OF TEST	DRY DENSITY		MOISTURE CONTENT (%)	CONFINING PRESSURE (psi)		MAXIMUM DEVIATOR STRESS (psi)		STRAIN RATE (% min)	BACK PRESSURE	
		FEET	METERS			pcf	kg/m <sup>3</sup>		ksi	psi	ksi	psi		ksi	psi
B-P-4	B-1	1.0 - 2.0	0.30 - 0.61	SP-SM	CD	100.4	1608	2.8	0.6	29	17.8	852	0.09	0	0
				SP-SM	CD	100.0	1602	3.0	1.2	57	9.7	464	0.09	0	0
				SP-SM	CD	99.1	1588	4.1	2.3	110	5.0	239	0.09	0	0
				SP-SM	CD	99.5	1594	3.6	4.6	220	2.7	129	0.09	0	0
B-P-7	B-1	1.0 - 2.0	0.30 - 0.61	SP-SM	CD	119.8	1919	11.7	0.6	29	5.3	254	0.09	0	0
				SP-SM	CD	119.9	1921	11.6	1.2	57	8.0	383	0.08	0	0
				SP-SM	CD	120.5	1930	11.5	2.3	110	14.2	680	0.10	0	0
				SP-SM	CD	120.3	1927	11.6	4.6	220	24.2	1159	0.08	0	0
				SP-SM	CD	107.4	1721	14.3	0.6	29	2.4	115	0.09	0	0
				SP-SM	CD	107.0	1714	14.8	1.2	57	4.0	192	0.10	0	0
				SP-SM	CD	107.3	1719	14.4	2.3	110	7.4	354	0.10	0	0
				SP-SM	CD	109.7	1757	12.0	4.6	220	13.7	656	0.10	0	0
				SP-SM	CD	96.8	1551	12.8	0.6	29	1.6	77	0.09	0	0
				SP-SM	CD	96.0	1538	14.5	1.2	57	3.0	144	0.10	0	0
				SP-SM	CD	95.2	1525	15.2	2.3	110	5.4	259	0.10	0	0
				SP-SM	CD	95.9	1536	14.4	4.6	220	11.7	560	0.09	0	0
				SP-SM	CD	115.8	1855	4.4	0.6	29	9.5	455	0.08	0	0
				SP-SM	CD	116.4	1865	4.1	1.2	57	14.1	675	0.08	0	0
				SP-SM	CD	115.9	1857	6.0	2.3	110	24.5	1173	0.08	0	0
				SP-SM	CD	115.2	1846	4.1	4.6	220	36.7	1757	0.08	0	0

SUMMARY OF TRIAXIAL COMPRESSION  
TEST RESULT, TEST TRSCK B, ETB MOBILITY  
STUDY, NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE BMO

TABLE  
C-2  
2 OF 2

**FLURO NATIONAL INC.**

AFV-10

CHECKED BY \_\_\_\_\_ APPROVED BY \_\_\_\_\_

SAMPLE NUMBER	SOIL TYPE	PERCENT PASSING #200	ATTERBERG LIMITS		SPECIFIC GRAVITY	MAXIMUM DRY DENSITY		OPTIMUM MOISTURE (%)	COMPACTED DRY DENSITY		COMPACTED MOISTURE (%)	PERCENT OF MAXIMUM DRY DENSITY	CBR (%)
			LL	PI		pcf	kg/m <sup>3</sup>		pcf	kg/m <sup>3</sup>			
B-P-4 (B-1)	SP-SM	7		NP	2.64	122.8	1967	10.0	114.0	1826	10.2	92.8	43*
									101.0	1618	9.8	82.3	1*
									113.0	1810	5.0	92.0	70
									107.0	1714	5.2	87.1	5
									111.3	1783	2.4	90.6	8
									101.0	1618	2.2	82.3	3
B-P-6 (B-1)	SP-SM	9		NP	2.63	117.2	1878	12.0	115.1	1844	4.8	98.2	81
									110.0	1762	5.0	93.9	56
									102.6	1644	4.9	87.5	12

\* SOAKED TESTS - ALL OTHERS UNSOAKED

CALIFORNIA BEARING RATIO (CBR)  
TEST RESULTS, TEST TRACK B  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - 800

TABLE  
C-3  
1 of 2

**FLUORO NATIONAL INC.**

USAF -08



SAMPLE NUMBER	SOIL TYPE	PERCENT PASSING #200	ATTERBERG LIMITS		SPECIFIC GRAVITY	MAXIMUM DRY DENSITY		OPTIMUM MOISTURE (%)	COMPACTED DRY DENSITY		COMPACTED MOISTURE (%)	PERCENT OF MAXIMUM DRY DENSITY	CBR (%)
			LL	PI		pcf	kg/m <sup>3</sup>		pcf	kg/m <sup>3</sup>			
B-P-7 (B-1)	SP-SM	10		NP		123.1	1972	10.8	116.0	1858	11.1	94.3	45*
									114.0	1826	11.2	92.6	39*
									109.7	1757	10.7	89.1	16*
									98.5	1578	10.5	80.0	1*
B-P-8 (B-1)	SP-SM	9		NP	2.66				115.2	1846	2.9	93.6**	63
									111.6	1788	2.9	90.7**	19
									100.1	1604	2.8	81.4**	1

\* SOAKED TEST - ALL OTHERS UNSOAKED  
 \*\* ESTIMATED BY USING MAXIMUM DRY DENSITY  
 OF 123.0 pcf (AVERAGE OF 122.8 AND 123.1 pcf)

CALIFORNIA BEARING RATIO (CBR)  
 TEST RESULTS, TEST TRACK B  
 ETB MOBILITY STUDY  
 NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
 DEPARTMENT OF THE AIR FORCE - DMO

TABLE  
 C-3  
 2 of 2

**FURRO NATIONAL, INC.**

CHECKED BY: APPROVED BY:

TEST PIT NO.	SAMPLE NO.	SAMPLE INTERVAL		SOIL TYPE	TYPE OF TEST	DRY DENSITY		MOISTURE CONTENT (%)	CONFINING PRESSURE(σ <sub>3</sub> )		MAXIMUM DEVIATOR STRESS(σ <sub>1</sub> -σ <sub>3</sub> )		STRAIN RATE (% min)	BACK PRESSURE
		FEET	METERS			pcf	kg/m <sup>3</sup>		ksf	kn/m <sup>2</sup>	ksf	kn/m <sup>2</sup>		
C-P-7	B-1	1.0 - 2.0	0.30 - 0.61	SP-SM	CD	109.7	1757	4.7	0.6	29	5.9	282	0.08	0
				SP-SM	CD	110.3	1767	4.0	1.2	57	9.7	464	0.08	0
				SP-SM	CD	109.8	1759	4.6	2.3	110	14.2	680	0.09	0
				SP-SM	CD	109.8	1759	4.3	4.6	220	19.9	953	0.10	0
				SP-SM	CD	97.8	1567	4.8	0.6	29	2.3	110	0.08	0
				SP-SM	CD	98.0	1570	4.6	1.2	57	4.2	201	0.09	0
				SP-SM	CD	98.2	1573	4.2	2.3	110	8.1	388	0.08	0
				SP-SM	CD	98.1	1572	4.2	4.6	220	14.8	709	0.08	0
C-P-3	B-1	1.0 - 2.0	0.30 - 0.61	SP-SM	CD	109.7	1757	12.5	0.6	29	3.3	158	0.10	0
				SP-SM	CD	109.4	1753	12.7	1.2	57	5.5	263	0.08	0
				SP-SM	CD	109.6	1756	12.5	2.3	110	10.0	479	0.10	0
				SP-SM	CD	109.9	1761	12.3	4.6	220	18.4	881	0.09	0
				SP-SM	CD	104.3	1671	11.9	0.6	29	2.4	115	0.10	0
				SP-SM	CD	103.8	1663	12.4	1.2	57	4.8	230	0.10	0
				SP-SM	CD	103.5	1658	12.8	2.3	110	7.9	378	0.09	0
				SP-SM	CD	103.9	1664	12.4	4.6	220	15.3	733	0.08	0
				SP-SM	CD	98.5	1578	11.6	0.6	29	1.7	81	0.08	0
				SP-SM	CD	98.4	1576	11.8	1.2	57	3.2	153	0.10	0
				SP-SM	CD	98.4	1576	11.7	2.3	110	6.0	287	0.10	0
				SP-SM	CD	98.2	1573	12.0	4.6	220	11.5	551	0.10	0

SUMMARY OF TRIAXIAL COMPRESSION  
TEST RESULTS, TEST TRACK C, ETB MOBILITY  
STUDY, NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE BMO

TABLE  
C-4  
1 OF 2

**TUGRO NATIONAL, INC.**



SAMPLE NUMBER	SOIL TYPE	PERCENT PASSING #200	ATTERBERG LIMITS		SPECIFIC GRAVITY	MAXIMUM DRY DENSITY		OPTIMUM MOISTURE (%)	COMPACTED DRY DENSITY		COMPACTED MOISTURE (%)	PERCENT OF MAXIMUM DRY DENSITY	CBR (%)
			LL	PI		pcf	kg/m <sup>3</sup>		pcf	kg/m <sup>3</sup>			
C-P-1 (B-1)	SP-SM	7		NP	2.61	107.3	1719	12.0	102.5	1642	11.8	96.5	32*
									98.9	1800	11.6	93.1	25*
									99.0	1596	12.2	92.3	21*
									108.7	1757	6.8	102.0	50
C-P-3 (B-1)	SP-SM	8				111.0	1778	12.5	108.6	1756	12.3	98.7	45*
									105.7	1683	12.5	95.2	20*
									91.7	1489	12.5	82.6	1*
									111.3	1783	6.6	100.0	57
									107.2	1717	6.8	97.0	49
									95.0	1522	6.7	86.0	11
									111.9	1793	4.8	100.8	78
									108.7	1757	5.4	98.8	56
									106.7	1709	5.6	96.2	49
									104.0	1686	5.0	93.7	21
						98.1	1572	5.1	88.4		5.1	88.4	8
						88.3	1415	5.8	78.5		5.8	78.5	1

• SOAKED TESTS - ALL OTHERS UNSOAKED

CALIFORNIA BEARING RATIO (CBR)  
TEST RESULTS, TEST TRACK C  
ETB MOBILITY STUDY  
NEVADA TEST SITE, NEVADA

MX SITING INVESTIGATION  
DEPARTMENT OF THE AIR FORCE - DMO

TABLE  
C-5

**INSTRON NATIONAL, INC.**